

9728 P390

Keep Your Card in This Pocket

Books will be issued only on presentation of proper library cards.

Unless labeled otherwise, books may be retained for two weeks. Borrowers finding books marked, defaced or mutilated are expected to report same at library desk; otherwise the last borrower will be held responsible for all imperfections discovered.

The card holder is responsible for all books drawn on this card.

Penalty for over-due books 2c a day plus cost of notices.

Lost cards and change of residence must be reported promptly.



Public Library

Kansas City, Mo.

3 1148 00632 181

100 HOUSES

DATE DUE

OCT 15 '51	<i>Q. 570</i>	<i>9/25</i>
Bookmobile		FEB 1 '54 46
OCT 27 '57		

— SELECTED DESIGNS FROM PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION FOR

A HOUSE FOR CHEERFUL LIVING

74
M
A

REINHOLD PUBLISHING CORPORATION
330 West 42nd Street, New York 18, New York

Copyright 1947

REINHOLD PUBLISHING CORPORATION

All Rights Reserved

Printed in the United States of America

LOTUS PRESS, INC., NEW YORK

F O R E W O R D

The job of preparing for and running a National Architectural Competition entails a lot of sustained intensive work, even with as few as 200 or 300 designs. When, as in the case of the Pittsburgh Competition, there are over 900 designs, submitted the duties of all parties concerned mount to staggering proportions.

Judging the drawings is serious business. Each design must receive concentrated simultaneous scrutiny by all the judges, and none may be passed over without a fair examination and appraisal. This means hour after hour of going through the drawings one by one, eliminating the less competent designs: sifting, sifting, sifting, until only the top quality remains. The drawings are thus gone over in great detail, weaknesses and strengths spotted, comparisons made and argued back and forth until at last the collective mind of the jury is made up and these ultimate decisions reached.

Over 40% of the drawings submitted in this competition come from registered architects, the list including some of the most distinguished men of the profession. It is fair to say that the winners reflect the preponderant trend in architectural thinking as indicated throughout the whole set of submissions. Not surprisingly, that trend is in the direction of planning better accommodations for the needs of contemporary living, and away from attempted conformity with the fashions and fetishes of the last century.

The results are shown in the following pages. We believe them to be of educational value both to competitors and non-competitors. There are many excellent and brilliantly planned ideas (as well as some faults) incorporated in the designs. While the prize and mention drawings included in this book were published in the magazine "Progressive Architecture" (Pencil Points) the designs in the second section have not been shown before. Their inclusion illustrates still further the trend in contemporary planning schemes.

All prize and mention designs represent the considered choice of a sincere and enlightened group of architects who thought in terms of what would constitute a happy and improved living environment to which "G.I. Joes" should be entitled rather than of what returning soldiers themselves may be expecting under the influence of their war-born dreams of times past. It is hoped "Joe" gets the benefit of the study that went into this competition. He deserves it.

MAY 29 1947

Kenneth Reid

JERY OCT 9 1950

C O N T E N T S

PROGRAM page 1

REPORT OF THE JURY page 2

JURY COMMENTS ON THE PRIZE DESIGNS page 4

FIRST PRIZE page 6

SECOND PRIZE page 8

THIRD PRIZE page 10

FOURTH PRIZE page 12


SPECIAL MENTIONS page 14

MENTIONS page 21

SPECIAL PRIZES FOR DETAIL page 39

NON-PREMIATED DESIGNS page 43

INDEX OF DESIGNERS inside back cover



Considerations of the Jury of Award

(1) The architectural merit of the design, including its regional suitability, and the ingenuity shown in the development of the plans to fit the requirements of the problem.

(2) Practicability and economy of construction.

(3) The intelligence with which the products of the sponsor are appropriately incorporated into the design.

(4) The special prizes will be awarded on the basis of the excellence of the interior detail shown on the drawing.

Quality of delineation and composition of the drawing will not have undue weight with the Jury.

PROGRAM

(As Originally Presented)

MANDATORY. The design of a house in which an average young American family in an average suburban residential community can make its permanent home in a world at peace. The client, an average fellow who may as well be called "G.I. Joe," is a man in his early thirties who has served in the armed forces of his country during the war. His wife has done her part by working in a munitions plant, while their two children—a boy of ten and a girl of six—have been farmed out with the grandparents. The assumption is to be made by competitors that since the war is finally over the reunited family is determined to have its own home. Joe has got his old job back and his employer, pleased to have him, has plans for his promotion. A respectable accumulation of war bonds plus a loan from a local bank under the terms of the G. I. Bill of Rights makes the fulfilment of the family ambition possible; so Joe takes the first step and looks up a good architect.

A reasonably priced quarter-acre plot in a newly subdivided, fairly level area is decided upon as the site for the new home. This lot is roughly rectangular with a frontage of 75 feet along the southerly side of a paved street running southeast-northwest. It is 140 feet deep to the rear property line where it adjoins a neighbor's lot on the next street. A local restriction says that no building may be placed nearer than 30 feet to the street or nearer than 15 feet to the side or rear lot lines. The usual utilities are available.

Joe and his wife have no preconceived notion of what their home should look like beyond desiring it to be up-to-date and attractive and suited to the local climate. While they are sympathetic to the healthy contemporary trend toward greater freedom in architecture they do not wish their home to be so unusual that it will be unduly conspicuous. They want light and cheerful interiors and are conscious of the feasibility today of having somewhat larger glass areas than were commonly used ten years ago. They depend upon their architect to advise them upon the building materials and equip-

ment to be used. They are, of course, interested in keeping within their budget but they know that maintenance costs must be considered as well as initial outlay. Mrs. Joe expects to do her own housework and is anxious that this should be made as easy as possible by good planning and thoughtful detailing, so that she may have more time to devote to her children from whom she had to be separated during the war. Like most homemakers today, she particularly wants her kitchen and bathroom accommodations to be colorful, convenient, and easy to keep spotlessly clean.

Careful study of the client's needs—in conjunction with his present resources, his income, and the local building costs—leads the architect to conclude that his plan must be limited to 1400 square feet of floor area disposed on one or two stories. Not to be included in this limiting figure are the necessary single car garage and an adequate heater room either above or below grade.

Competitors are expected to provide for the comfortable and economical housing of the client and his family within the prescribed limits of area. Disposition of indoor and outdoor space, number of rooms, circulation, and accessories are left to the discretion of the designer.

Since G.I. Joe's number is legion, and since he may be found after the war in any part of the United States, it is left to each competitor to determine the locale in which his client is assumed to live. This chosen location must be clearly designated on the drawing and the Judges will take into account the regional suitability of the design. The sponsors, while naturally desirous of promoting the increased use of their products, are anxious that competitors shall use common sense and avoid extravagance in the disposition of these products. The designs will, it is hoped, show houses that might be appropriately built by the average family described in the program, at a cost of between sixty-five hundred and eight thousand dollars. This cost range is merely a suggestion and not a strict limitation in either direction.



NORMAN FLETCHER (left) and
JEAN BODMAN FLETCHER

FIRST PRIZE

REPORT OF THE JURY

A pretty fair reflection of the actual and potential architectural design performance in the United States today was evident in the nine hundred odd drawings submitted in the PENCIL POINTS-Pittsburgh Plate Glass Company Competition.

To the Jury it seemed that entirely too many were of such inferior quality as to suggest a discouraging outlook for G.I. Joe's postwar home. Although almost half of the designs came from registered architects, who should be presumed competent to do good architecture, there was a pronounced lack of good taste and sound realism. Of course, it must be admitted that the same observation applies to the general quality of existing houses throughout the country.

There may be several reasons for the prevalence of this distressingly low standard of house design. For one thing, many capable young men are now at war, and for another, there is a definite lack of understanding among many of the older architects as to the nature of the new trends in architecture. Many of them seem to think that modern design is just another "style."

The Jury felt a deep responsibility not only to the competitors but to the public as well. Their goals and guideposts were pretty well stated in the preamble of the Program. "To bring up to date, in line with recent technical advances, the general understanding of the ever present problem of planning the small homes of the nation." "To discover and give recognition to new design talent."

Since it was planned that the premiated designs were to be widely publicized, the Jury conscientiously tried to select not only the best solutions to

the problem as stated, but also the best in planning, in taste, and in detail. Established public prejudices, what would sell more easily, etc., were not considered pertinent. We sought rather to find what came closest to solving in a better, more realistic, and sympathetic way the problem of planning the small home.

One cannot say that the premiated designs *completely* solve this problem, because there are many important factors that a competition drawing cannot possibly include; especially when so little time and space are available.

From the Program requirements, it was obvious and right that there would be a limitation as to the scope and size of the house. With the exception of the square footage restriction, this limitation was not strict, but rather flexible. On costs, wide latitude was given, on the theory that increased use of new construction methods and materials might bring substantial reductions.

A consensus statement as to what the Jury was looking for in the house designs might be something like this: A simple direct solution which would give to the average small family a place in which it could live with greater comfort and freedom from drudgery than ever before. Several ideal characteristics agreed upon were:

- (a) Lack of pomposity.
- (b) Economy, both in initial and maintenance costs.
- (c) Provision for better facilities and amenities than the conventional type of house has heretofore supplied.

The question of "undue conspicuousness" and homogeneity of architectural "character" were discussed at length. We decided that the prevalent idea that



I. M. PEI (left) and
FREDERICK G. ROTH

SECOND PRIZE



a building in order to be in harmony with neighboring structures must be of the same "style" or "period" is erroneous.

The true *tradition* of all great periods in architecture has been *not* to copy past styles. For instance, in Pisa an unfinished Gothic chapel was completed during the Renaissance. The architects had such great respect for the work of the original designer that they didn't think of trying to imitate existing work. They completed the building in the Renaissance manner with such a sympathetic understanding and appreciation of what the original started out to be that only an archaeologist could detect today the difference between the two parts of the building.

Florence is noted for its homogeneity of architecture. Her buildings of many centuries—eleventh to twentieth—exist side by side harmoniously and inconspicuously. There are many historic examples of this sort.

In the average American neighborhood a very well designed house might be unduly conspicuous simply because it would be so much better than the usual mediocre average. There seems no good reason why a well designed contemporary house cannot fit in harmoniously with well designed houses of other periods, provided both are essentially good, and provided the materials used are homogeneous. The important things are not picayune uniformity or dull authenticity but the successful application of the good things at hand, similarity of materials and scale rather than of forms or details, and a genuine honesty of expression regarding our own times and our own lives.

In the Jury's discussions there arose the perennial question about the prohibitive expense of curtaining

material for large glass areas. We take this opportunity to spike this shibboleth of the archaeologist and interior decorator. Satisfactory curtains need not be expensive. Burlap, cotton sacking, unbleached sheeting, and mattress ticking are used extensively by those who are not taken in by the fabric industry. These materials, costing from twelve cents to thirty-five cents a yard, can be dyed or used as they come and are capable of most successful results. Curtains can be easily made at home, or can be made up outside at low cost. In fact, their cost on the whole is lower than that of window shades. The total cost of a glass wall properly detailed with such economical draw curtains is no more than the ordinary outside wall of the same area including a small window, shade, and chintz draperies.

All drawings submitted were considered at least twice. Those that remained in the last one hundred were studied many times. In making their selections the Jury considered the following:

- (1) The use of the site.
- (2) Simpler housekeeping.
- (3) Improved facilities for daily family activities.
- (4) The relation between the needs of children and adults.
- (5) Orientation and relation of indoor to outdoor space.
- (6) Privacy.
- (7) Appropriate use of materials.
- (8) Equipment.
- (9) Cost indication including initial cost versus maintenance.
- (10) Suitability to particular climate indicated.
- (11) A better "living surrounding" for the average small family.



Drawings of these four special mention designs, selected by the Pittsburgh Plate Glass Company for use in their advertising, were prepared by Ted Kautzky.



JURY COMMENTS ON THE PRIZE DESIGNS

1. The organization of this plan and its relation to the site are outstanding, and the Judges were unanimous in awarding it the prize.

The living and indoor "work-play" areas are nicely separated though still convenient to each other. Each has its own outdoor space.

The kitchen is actually in the heart and center of the house from which both the active outdoor areas can be surveyed. This permits easy supervision of children's play, easy access to service and drying yard, and to the social court.

The bedroom wing, which includes the study, is logically placed at the rear, where it opens out onto a less active environment. The solid walls are nicely arranged to give privacy from neighboring lots, the street, and even from the naturally noisy areas within the scheme itself.

Thus, the three separate functions of a house—activities, work, and relaxation—are clearly defined and arranged in a very practical form.

2. This house exhibits the quality of an easy directness and of purposeful planning.

The roof plan is essentially a square. Thus the outline of the building's shape is simple and interest is obtained by undercutting for the car shelter, piercing the roof for a court on the front, and extending it slightly for the outdoor play porch.


The plan is generally well conceived. The large area facing the rear of the lot is cleverly divided, retaining the inherent spaciousness, yet using the space for varied purposes. Fireplace and desk separate the study from the living room. The kitchen has a double outlook—onto the attractive entrance court and through the dining area to the rear garden by means of an open-top counter wall. A sliding glass arrangement screens the living room from cooking odors and kitchen noises.

Family play and hobby space is nicely segregated by the kitchen projection and by the depressed wall for the planting area.

3. The whole conception of this house is as brilliant as it is unusual. It makes use of a simple rectangular plan with various undercuts and screen projections. The central core, consisting of kitchen and heater room flanked by two bathrooms, is located on the side of the house nearest the lot line, with high windows for privacy. The relationship of the master bedroom and living area makes it possible to open the bedroom into the living room, thus giving larger visual space. The children's bedrooms, their indoor and outdoor play space, are well located for supervision although separated from the general living area.

The glass wall along the southeast side is intended to have obscure and semi-obscure panels. It might have panels made of wood or fabric or screens, which could be interchanged at various seasons of the year, thus giving either open space or closed-in privacy. The structure, although somewhat dubious in engineering, could certainly be made practical if structural members were slightly heavier. The use of stone, wood,

Designs shown: upper left, by Karl J. Belser and Karel H. Dekker; lower left, Alexis Dukelski; upper right, Leon Hyzen and Allmon Fordyce; lower right, Oliver Lundquist.



and corrugated asbestos called for would make for an interesting and pleasing effect. Contrasts between the irregular rubble, the rigid rhythm of the corrugated material, and the transparency and smoothness of the glass give an unusual and desirable variation in texture.

4. Basically, this plan should be the most economical of all. It is a square with the mechanical core in the center. Thus, there is more floor area in proportion to outside wall area. Actually, with the materials called for, it would be costly to construct today.

The plan arrangement is good. The children's sleeping and play room is large and is under direct supervision from the kitchen. The adult sleeping and dressing room is equally large and well arranged. Certainly the relationship of adult's and children's activities has been well thought out.

The varying, receding planes and the subtle relationship of textures, or open and closed walls, give a sense of space

that is unusual in a house of this size.

It was felt that, although this house was in no way limited to this or any other piece of property, it might be prefabricated and built anywhere in the U. S. on a site with any orientation; but even though this is a valuable asset, the orientation in this instance is wrong—possibly not so much from the sunlight point of view (since it is designed for Southern California) but because the house is placed too close to the street for this to be excusable. As one dissenting member of the Jury put it, "The designer completely ignored the site."

Respectfully submitted,



**JURY OF
AWARD**

Pietro Belluschi
Ralph Flewelling
J. Byers Hays
Robert M. Little
Louis Skidmore
Philip Will, Jr.
Hugh A. Stubbins, Jr.,
Chairman

Additional comments and criticisms by the Jury will be found on the following pages, along with reproductions of the Prize and Mention designs. In the case of the Mentions, the captions were written by the editors, but are based on comments made in the Jury room during the Judgment.

KEY TO MARKING OF DESIGNS

1.	FIRST PRIZE
2.	SECOND PRIZE
3.	THIRD PRIZE
4.	FOURTH PRIZE
SM	SPECIAL MENTION
M	MENTION
SP	SPECIAL PRIZE FOR DETAIL



JEAN BODMAN FLETCHER & NORMAN FLETCHER
1430 MASSACHUSETTS AVE.
CAMBRIDGE, 38, MASS.

1st


ADDITIONAL JURY COMMENT

"The design is sympathetically done; it is simple, direct, and has a definite American flavor that is refreshing.


"The method of building—that of purchasing a prefabricated mechanical core and adding the other amenities—is not a new idea. It is reasonable and cleverly done, but was not a deciding factor.

"The open passageway between living and sleeping areas was questioned. This is conceivably all right for some California locations, and the addition of a glass wall would eliminate any objection.


"Perhaps the lavatory would have been more useful had it been placed where the heater room is, thus allowing children to reach it more easily from the play yard. Also, the addition of a door from play yard into the bedroom corridor would be useful. As in a number of the designs chosen for awards, there is a lack of adequate storage space."





The authors say of their design, which is intended for Salinas, California, "Joe wants to help build his own house, but also wants it technically up-to-date, so with the aid of an architect, a building supervisor, and a special booklet he starts. He has chosen this plan out of a group of plans similar in idea. First he goes to the factory to get the 'mechanicore' which has all the latest conveniences, and then to the mill for lumber. Joe can use stud construction or simple plywood panels. The core is attached to the street utilities, the concrete slab is poured, and Joe can start erecting the walls. The neighbors help Joe, and later Joe helps them. Joe and family can now start making the house a home."




PLAY YARD ELEVATION



STREET ELEVATION







ADDITIONAL JURY COMMENT


"This house has the necessary facilities for all daily activities and they are arranged for easy upkeep and cheerful living. Wood and glass are used with great skill to produce elevation forms that are strong, clear, in good proportion, and pleasant to look at. The design was criticized for the obvious lack of privacy in the bedrooms, since they face and are very close to the adjacent lot. The detail (see page 41) of the sliding counter window was commended as an intelligent use of glass, simply and cleanly executed."

2nd **FREDERICK G. ROTH**
 2625 NO. SECOND ST.
 MILWAUKEE 12, WIS.
 & I. M. PEI
 14 OLD DEE ROAD
 CAMBRIDGE, MASS.





*

This house is intended for the Middle Atlantic Seaboard. Designer specifies exterior of vertical tongue and groove siding, and interior of the same material with some plywood panels. Roof to be asphalt felt built-up roofing insulated with Foamglas. Windows facing northwest and northeast to be Twinow units. Glass surfaces exceeding D.S.A. limits to be polished plate glass. Overhanging sunshade on southerly side to be 1/4 inch Coolite. All built-in conveniences to be standardized units of plywood construction.







S E

N E



DRIVEWAY



ADDITIONAL JURY COMMENT

"There was some argument whether this building would be unduly conspicuous, and the consensus was that it would be conspicuously good, though admittedly expensive. The house was criticized mainly for its too romantic approach to structural requirements and for a certain lack of privacy.


"The bent solex glass detail for the skylight (see page 42) was considered a practical and intelligent application of glass for its purpose under the conditions."





"Interior walls are of similar standardized panels painted neutral. All cabinets and storage units standardized and based on a ten-foot module. All furniture and storage units are light mobile type with nothing built-in or static. Floor construction concrete slab laid on grade with radiant floor heating pipes and coils in slab. Roof of light metal cell panels spanning between light steel bents, spaced ten feet on centers and supported by tubular V-columns. Walls non load-bearing. Insulated roof panels covered with corrugated asbestos roofing."

3rd RALPH RAPSON
645 N. MICHIGAN
CHICAGO 11, ILL.

This design is intended for any locality in the southern half of the United States. The designer says, "This plan and the plot are an integrated unit. The plan is predicated on these basic considerations: that there is need for separate yet closely interlocking quarters for adults and growing children; that food preparation and its consumption are the 'heart' of the living activities and should form the interlocking link between the adult and children areas, thus evolving three basic areas with the possibility of one large uninterrupted space or three separate functional units; that the indoor and outdoor activities should be fused, with emphasis being laid on a healthy active type of living rather than a passive one."






**PLOT
PLAN**

The designer calls attention to cross-ventilation through the whole house, which is intended for the California climate. The house is based in part on studies in the field of abstract art, involving the manipulation of space by interpenetration, division and the use of color combined with opaque, translucent, and transparent materials to control spatial light and shadows.

4th


**EDUARDO FERNANDO CATALANO
HOLMBERG 3483
BUENOS AIRES, ARGENTINA**



ADDITIONAL JURY COMMENT

"The design, though elegant, is slightly overdone and seems somehow more of an 'imported' than an 'American' product. It was the subject of much debate but was awarded a prize by a majority of the Jury chiefly for its ingenious plan.

"The portion of the detail which is a glass sandwich—Carrara glass enclosing Foamglas slab—though at present expensive, may some day prove to be an ingenious and practical solution to the 'complete wall' problem. The rest of the detail, glass block and glass louvers, seems overly complicated." (See page 39.)




THIRD ELEVATION

THE ELEVATIONS ARE BASED UPON THE DIVISION OF THE SURFACE OF A STANDARD STEEL FRAME, INTO SUBORDINATE RECTANGLES OF WHITE, BLACK AND PURE COLORS ACCORDING TO LIFE REQUIREMENTS



FOURTH ELEVATION




KEY TO PLAN

1. Supplementary space for breakfast. 2. Space for refuse and cleaning tools inside the house. Provision for refuse and gardening implements outside the house. 3. Kitchen, laundry, bath-room form one unit with the boiler room, which is placed in the middle of the house and has a common smoke stack with the fireplace, as


well as access from the kitchen. 4. Uses of glass to create space. In the kitchen wall it produces an illusion of space and serves in a practical way as a control over children's activities. 5. A flexible view through this wall is regulated by curtains. 6. Laundry, bedrooms, bathroom, and ironing unit with easy access to linen supply. Separation between living and

sleeping areas. Back door provides exclusive access to sleeping area. 7. Light from skylight. A Boiler. B Living room. C Study and place for children's games. D Dining room. E Bedroom. F Kitchen laundry 11.6 x 7.6. G Bathroom 6.6 x 7.9 4.6 x 4. H Garden. K Garage. L Interior gallery. M Dressing room. N Main entrance. P Rear entrance. R Street.



Highlights noted in this design for a California home; compact plan, minimum waste hall space to clean; economical to build and maintain; most partitioning made up of useful storage space; fine, large related living and dining space on southern garden front; side walls and windows thoughtfully worked out for privacy from neighbors; well planned plot, thoroughly put to use; clerestory for cross ventilation and lighting of bath, hall, and kitchen. Criticisms: kitchen not well placed for supervising children's outdoor play; exterior lacks "positive" character.


KARL J. BELSER
UNIVERSITY OF OREGON
EUGENE, OREGON
& KAREL H. DEKKER
LOS ANGELES CITY HALL
LOS ANGELES 12, CALIF.




ALEXIS DUKELSKI
11009 1/2 STRATHMORE DRIVE
LOS ANGELES 24, CALIF.

SM


"The plan has many delightful ideas," one juror said, "but the designer made it most difficult for the jury to discover the good points by much too much complicated indication." Among the good points: outdoor porches off the bedroom suites (the latter seem cramped in area; however); the walled outdoor dining room for use in summer (the house is for the Northeast); the "human quality" of the design; the basic economy of arrangement for a normal family's activities; provisions for privacy. "Too much stone" on both horizontal and vertical planes was a criticism.



PERSPECTIVE




PLAN




SOUTH WEST ELEVATION



SOUTH EAST ELEVATION




B




A	44' x 27'	1188
B	175' x 85'	149
C	113' x 8'	52
D	114' x 3'	21
E	10' x 3'	30
TOTAL		1380 SQ FT

COMPUTATION



DETAIL



A



REGION: NORTH-EAST


PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION

The one that just missed a prize award. The best of several drawings that used a similar basic plan, the design was admired by the jury for its domestic quality, the economical arrangement of living, kitchen-utility, and sleeping areas, and the simple, unaffected approach to the problem. Criticized were the many shapes and sizes of windows which, some jurors felt, resulted in lack of harmony. Arrangement of plot and relation of outdoor areas to separate indoor functions were praised. For the Northeast.

SM

LEON HYZEN
RM. 901 PALMOLIVE BLDG.
CHICAGO, ILL.
& ALLMON FORDYCE
166 E. 95th ST., N. Y. C.

Pencil Points Pittsburgh Architectural Competition




STANLEY A. KAZDAILIS
4319 SO. MAPLEWOOD AVE.
CHICAGO 32, ILL.

SM

Things admired in this design for living in the central Midwest were the separate provisions for adult and children's needs, including physical separation of the bedrooms; the domestic scale of the design and the simple exterior character. Things questioned or deplored: the service area was not planned for child supervision; poor disposition of land, with unnecessarily wasted front lawn; and (lacking any plan indication to the contrary) no provision for privacy from view of next-door neighbors. The detail of open plumbing, openly arrived at, raised several eyebrows.

PENCIL POINTS-PITTSBURGH ARCHITECTURAL COMPETITION


Handwritten signature



Designed for the central eastern states, this scheme on three half-levels results in a small house with an extraordinary sense of spaciousness; but, as one juror put it, despite the fact that the designer specified acoustical surface treatments, "the lounge and the children's bedrooms could never be quiet if the work and recreation area was used intensively enough to justify the amount of space given to it." Also criticized was what appears to be the quite arbitrary introduction of stonework on exterior walls. Location of family rooms toward rear garden would ensure privacy.

SM




OLIVER LUNDQUIST
1703 21st ST. N.W.
WASHINGTON, D. C.



Architectural drawings of a glass partition between a kitchen and living area. The drawings include a plan view from the living room, a section view, and a view from the alcove. Key features include a glass partition with a double-glazed section, a kitchen cabinet, a dining room screen, and a view from the alcove showing a large circular opening. Labels include 'VIEW FROM LIVING ROOM', 'SECTION', 'VIEW FROM ALCOVE', 'GLASS PARTITION BETWEEN KITCHEN & LIVING AREA', 'DOUBLEGLAZED PARTITION', 'DETAIL A', 'DETAIL B', 'DETAIL C', 'DETAIL D', 'DETAIL E', 'DETAIL F', 'DETAIL G', 'DETAIL H', 'DETAIL I', 'DETAIL J', 'DETAIL K', 'DETAIL L', 'DETAIL M', 'DETAIL N', 'DETAIL O', 'DETAIL P', 'DETAIL Q', 'DETAIL R', 'DETAIL S', 'DETAIL T', 'DETAIL U', 'DETAIL V', 'DETAIL W', 'DETAIL X', 'DETAIL Y', 'DETAIL Z'.

SM

10




pencil points - pittsburgh architectural competition




longer
middle Atlantic states




first floor 680
second floor 110
total 1094 square feet




interior elevation



section



exterior elevation




composite plan

Main rooms sheltered from street and northwest by barrier walls on first floor and (on second) by hallway location; toward the southeast, walls are glazed. Splayed living room wall increases southern exposure; screen fence gives privacy from neighbors. Kitchen has full view of terrace and yard. Abbreviated partitioning limits indoor privacy but simplifies housework. Bedrooms have desk and shelf space as well as closets; the deck is for sunbathing. Storage and heater in basement. Middle Atlantic climate.

SM



CHARLES D. WILEY
1000 NORTH STATE ST.
CHICAGO 10, ILL.



Location of entrance provides direct circulation to living area, kitchen, and bedroom wing. Minimum partitioning reduces housekeeping drudgery, while central location of baths shields children's bedrooms from living room sounds. Roof overhangs precisely calculated to screen out excessive sun. Exhaust fan draws house air through grilles above baths into plenum; hence into attic space and eventually to outlet in roof soffit near entrance. Good general storage space along garage wall. Designed for Texas climate.


M

DONALD BARTHELME
BOX 262, ROUTE 12
HOUSTON 6, TEX.




PLOT

LOCATION
PENNSYLVANIA



PLAN




BASEMENT



DEVICE




NE




A 443.370-16402
B 18.5-7.5 101.3
C 16.47-90 140.9

A 16402
B+C - 2472
TOTAL -15980




NW



DEN

DINING



PLAN (A)

SECT (B)





**PENCIL POINTS
ARCHITECTURAL**

**PITTSBURGH
COMPETITION**

In this house designed for Pennsylvania, the arrangement of the entrance hall and stair to the basement effectively separates children's rooms from living quarters. The huge corner window walls flood living area with light and sun, automatically controlled by roof projection; interior corner placement of dining space, although lighted by clerestory and borrowed light from hallway, seems unfortunate; the efficient kitchen-laundry might also have been better placed for serving terrace and supervision of play.

M

**BERNARD L. CAMPBELL
2400 MARKET ST.
HARRISBURG, PA.**



BATHROOM DETAIL 3/4"

nom de nom

- fluorescent light
- adjustable fixture
- plate glass mirror
- window
- glass shelves
- counter-type sink
- structural glass
- vanity drawers



50	56	20
4.14	791	20
2.0	30	21
		56
		56
		414
		791
		1375

PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION

W. BROOKS GAVIN
8310 10th ST.
SILVER SPRING, MD.

M

In this two-story solution (leaving maximum land for outdoor living), planned for the middle Atlantic states, interior living space is divided into dining-kitchen, and play space on the ground floor, and a quiet family sitting room upstairs. The latter seems too enclosed; one end is merely a passage which children would have to use to reach bedrooms. The first floor suffers by too great recessing to gain overhangs at front and back; also exterior lacks "human quality" found in some of the other designs.



PLAN - BOOK CASE & GLASS CASE BETWEEN KITCHEN & LIVING AREA


PENCIL POINTS PITTSBURGH - ARCHITECTURAL COMPETITION




Non-bearing interior divisions are made up of storage units or incidental screens which can be arranged with relative ease. The children's play area may be supervised either from the kitchen or (through a glass screen) from the dining end of the living area. Separation of adults' bedroom and children's quarters would appeal to many; placement of the children's rooms just the other side of the wall of the living area, however, suggests noise difficulties. The plan fails to indicate how the owners would obtain privacy from near neighbors. Designed for northern California.

M

C. N. CHAU
1115 EAST 82nd ST.
CHICAGO, ILL.



PERSPECTIVE




COMPUTATIONS

A-150' X 46'-0" = 720 SQFT
B-350' X 10'-0" = 660 SQFT
TOTAL 1380 SQFT

"MAKE THE SAN FERNANDO
VALLEY MY HOME"

PLANS




NORTH




EAST



ELEVATIONS



WOMEN'S BATH DETAILS




DETAILS

PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION


A. ALBERT COOLING
184 ACARI DRIVE
LOS ANGELES 24, CALIF.

M


The large amount of corridor space was criticized. Combination living-dining-kitchen-laundry, admitted as an acceptable plan for many families. Despite laundry-dryer equipment, however, some outdoor drying yard should probably have been provided. Large hobby-playroom with fireplace adjoining terrace, a fine facility seldom found in the "average" house. Interesting bedroom-window detail: fixed central sash, ventilating louvers below, operable transoms above. Planned for a southern California site.



GEOGRAPHIC LOCATION - SOUTHWEST



SECOND




FIRST


AREA TABULATIONS		
A	12' x 18'	-107.5
B	12' x 18' (1/2)	-107.5
C	15' x 20'	-430
D	3' x 20' (1/2)	-465
E	3' x 5'	-15
F	18' x 31'	-558
G	NOT INCLUDED	
TOTAL		1593.5




NORTHWEST ELEVATION



SOUTHWEST ELEVATION




FIRST FLOOR





SECOND FLOOR

1 LIGHTWEIGHT METAL FRAME
2 CONTINUOUS PLUG-IN STRIP
3 ADJUSTABLE LIGHTING UNIT
4 TEMPERED TRANSLUCENT GLASS
5 EVERSEAL GLASS TAPE
6 CONCEALED ELECTRIC CONDUIT
7 SUB-FLOOR ELECTRIC DUCT
8 SUPPORT-CONNECTION TO DUCT
9 FIN. FLOOR
10 FIN. CEILING
11 CONNECT. TO UPRIGHT SUPPORT
12 GLASS BLOCK PARTITION



DETAIL

A LIGHTWEIGHT METAL FRAME.
B CONTINUOUS PLUG-IN STRIP.
C ADJUSTABLE LIGHTING UNIT.
D TEMPERED TRANSLUCENT GLASS.
E CABINET WITH SLIDING DOORS.
F STEEL T₁ SCREWED THRU GLASS.
G EVERSEAL GLASS TAPE.
H CONCEALED ELECTRIC CONDUIT.
I SUB-FLOOR ELECTRIC DUCT.
J SUPPORT-CONNECTION TO DUCT.
K FIN. FLOOR L FIN. CEILING.
M CONNECT. TO UPRIGHT SUPPORT.
N GLASS BLOCK PARTITION.






PLOT PLAN

PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION



Designed for the Southwest, this house has a compact and well related arrangement of living, dining, and play areas, with a conveniently located kitchen-laundry-service unit. Second floor plan is good but likely to be expensive. Flaws include inadequate storage space, scattered plumbing, and poorly located heater room with questionable stair head-room. Exterior is to be of rough redwood boards and battens. Rumpus space and children's rooms to be closed against weather by sliding glass doors.

M


SEYMOUR R. JOSEPH
1841 BROADWAY
NEW YORK 23, N. Y.





DETAIL OF WINGED GLASS PANELS BETWEEN LR & DA/STUDY/PLAY AREA




BED ROOMS
11'6" x 12
11'6" x 12
9'6" x 12
BATHS
11'6" x 7'6"



PLOT (IN VIRGINIA)



BASE




V.... PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION

VINCENT KLING
ENGLISH VILLAGE
CRANFORD, N. J.

M


This house planned for a Virginia location is one of comparatively few that included a basement for the heating equipment. The living room is screened from the front door, and even the stairs can be used without disturbing living room activities. Kitchen-laundry well located for access to dining space, terrace serving, and drying yard. The house also appealed to the jurors as being agreeably domestic in both scale and character.

Architectural drawing of a modern house, likely a residence designed by Frank Lloyd Wright. The house features a flat roof, large windows, and a prominent brick chimney. The drawing is a black and white line sketch, showing the house from a side-on perspective. The house is surrounded by trees and landscaping, including a large tree on the left and a smaller tree on the right. The drawing is titled "PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION" in the top left corner.




M

30




PERSPECTIVE FROM SOUTH




PLOT PLAN

LOCATION MIDCENTRAL STATES




A	36'-0" x 19'-6" = 702
B	12'-0" x 15'-6" = 186
C	18'-6" x 21'-9" = 424
D	12'-0" x 3'-0" = 36
	1348
LESS	
E	6'-0" x 4'-0" = 24
TOTAL	1324

AREA




PLAN



NORTHWEST



NORTHEAST





PENCIL POINTS-PITTSBURGH ARCHITECTURAL COMPETITION

C. STUART PERKINS
RR #3
WAYZATA, MINN.



M

One of the more imaginative of several designs with similar basic scheme. Centralized entrance and heater room; separation of living areas into active and quiet (the latter further separable for use as guest room); flexible two-in-one treatment of children's rooms, and greatly increased bathroom facilities provided by partitioning and inclusion of one added piece of equipment; all were admired. Questioned was location considered for outdoor laundry drying; planting on northeast and carport wall on southwest seemed ample screen from neighbors. For midcentral states.


**PENCIL POINTS
PITTSBURGH
ARCHITECTURAL
COMPETITION**




FIRST FLOOR



SOUTHEAST




SECOND FLOOR




FLOOR AREA CALCULATION

HOUSE DESIGNED FOR
THE
GREAT LAKES REGION




NORTHEAST



PLOT PLAN
1/4" SCALE



STONE DETAIL
Showing use of 16" stone, course
and chain of stone.



SECTION SHOWING PLANTING
AND STAIRCASE (TO FIRST)

ELEVATION FROM TERRACE DOOR

ELEVATION FROM TERRACE DOOR


MON-DE-GUERRE



Planned for Great Lakes region, this spacious, small house was considered one of the better two-story solutions (in general, the jury considered one-story schemes better answers to the program). Projecting second floor, probably expensive, produced gracious sheltered entrance by either car or foot on street front and loggia toward garden. Arresting features: glass-enclosed stairway; projecting living room window, including plant bay, view window, and solar-heat advantages. Guest-study-play room at top of stairs gives added livability; storage, ample and well located.

M


**FREDERICK G. ROTH
2625 NO. SECOND ST.
MILWAUKEE 12, WIS.
& I. M. PEI
14 OLD DEE ROAD
CAMBRIDGE, MASS.**




The angling of the plan to catch maximum southern sun was admitted, but the resultant awkward shapes of master bedroom and living room were criticized. The plan provides barrier between activity and sleeping areas; the kitchen and laundry equipment is complete—and expensive. Amount of window wall appealed to the jurors as excessive and was sharply criticized (lacking plot plan indication) for lack of privacy from neighbors. Nonetheless, logical separation of areas for "in flow," working, sleeping, and activity kept this design constantly to the fore. Midwest location.

M

DOUGLAS C. SIMPSON
21 FIRST AVE.
OTTAWA, ONTARIO, CANADA
& EDWARD P. ELLIOTT
COOLIDGE LANE, DEDHAM, MASS.




SOUTH PERSPECTIVE



NORTH EAST
ELEVATIONS

NORTH WEST



FLOOR PLAN AND PLOT PLAN

PLAN SCALE 1/4" = 1'-0"

HOUSE IN SOUTHERN CALIFORNIA


AREA CHART

PLAN SCALE 1/4" = 1'-0"

TABLE OF AREAS

A	19'2" x 3'8" = 728.08
B	6'6" x 6'0" = 19.5
C	10' x 23'2" = 231.6
D	13'8" x 29'0" = 396.14
	1375.32

TOTAL AREA 1376 SQ. FT.



ELEVATION

PLAN

GLASS DETAIL

DRESSING ROOM

SECTION


DETAIL OF DRAWER

PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION

A "good, conservative plan," it was nevertheless criticized for having more circulation space than a house of this size should afford. All main living rooms would have excellent orientation, and the fence and planting indications suggest that the designer has planned for sufficient privacy. A criticism was that no interior play space was provided, and it was not clear if children's outdoor play could be supervised from the kitchen window. The modest scale, simple detail, and contrast of materials in the elevations were particularly admired. Designed for southern California.

M


E. W. WAUGH
GEORGE MATSUMOTO, &
CHARLES T. GRANGER
WEST LONG LAKE ROAD
BLOOMFIELD HILLS, MICH.



NORTHEAST ELEV



NORTHWEST ELEV




PRE-FABRICATED
HOUSE - BUILDING SYSTEM




REGION


NE



PLAN



SECOND FLOOR




6.3^{LB} CORRUGATED
GLASS

AN
ADJUSTABLE
WINDSCREEN



STEEL BOLT—
WOOD BLOCKS
CORR GLASS
HINGE




PLAN SECT ELEV



FIRST FLOOR



PLOT PLAN 1/2" = 1'-0"




PENCIL PTTS- ARCHITECTURAL POINTS BURGH COMPETITION

FRANK WEISS
1412 W. LINDLEY AVE.
PHILADELPHIA, PA.

M



An economical, two-story plan, this house was designed for the Northeast. Some jurors felt that inclusion of so many types of prefabricated panels—some with glass lenses or block; others of plywood, plywood covered with canvas, or vertical wood sheathing—resulted in rather confused elevations. In general, plan elements are well disposed, but challenged were the cross-hall relation between kitchen and dining area and the living room's lack of protection from the front door. The large storage-heater room is a sensible provision—one, surprisingly, that many other designs lacked.



SOUTH EAST



NORTHEAST



A HOUSE IS A SOCIO-LOGICAL THING. IT IS A MEN OF DEMO-CRACY IT IS ALSO AN OUTPOST

TO THE HOUSE COME THE PRODUCTS OF SOCIETY: DRAMA, FACTORY, THE ASSEMBLY THE TRAFFIC IS VERY HEAVY.

THE AIM IS TO HEIGHTEN THE DEGREE OF AWARENESS OF THE CO-EXISTENCE OF THOUGHT (PURPOSE) AND ACTION (SENSUALITY)

THE ARCHITECT AS SOCIOLOGIST SEEKS, SELECTIVELY, TO FORM THE APPROACH TO A HIGHER REALIZATION OF THE CULTURAL IMAGE



STANDARD HOUSEHOLD

CONTEMPORARY REQUISITES

THE SHAPING OF SPACE TO PERMIT SEPARATE AGE-GROUP ACTIVITY, SOCIAL, LOCAL, GATHERINGS AND THE FIREPLACE. A WORKSHOP, FINE DRESSING - THE HOUSE BE-COMES A MICROCOSM A WEAVING OF ART AND LIFE

MAN IS THE MEASURE OF ALL THINGS

GLASS BLOCK SKYLIGHT



PENCIL POINTS_PITTSBURGH ARCHITECTURAL COMPETITION

In this compact plan, for New England, the designer managed to include an extraordinary number of living facilities—play and hobby space in addition to the usual functional areas. But, in detail, the jury found many things to criticize: lack of privacy for individual members of the family; the fact that the dining space overlooks the service yard; the apparent use that would have to be made of the living room as a corridor, and the very questionable placement of the bathroom which “creates more corridor space than it saves” and which is “screened from view but not from sound.”

M

FRANK WEISS
1412 W. LINDLEY AVE.
PHILADELPHIA, PA.

SP

EDUARDO FERNANDO CATALANO
HOLMBERG 3483
BUENOS AIRES, ARGENTINA

POLISHED PLATE GLASS, GLAZING $\frac{1}{4}$ IN.
PITTSBURGH COPPER BACK STRUCTURAL MIRROR,
PITCO PX 123
 $\frac{1}{4}$ IN. OF CLEARANCE
 $\frac{1}{4}$ IN. OF MASTIC
INSULATING MATERIAL,
DAMP-PROOF PAINT
WOODEN FRAME
FOAMGLASS 2 IN.
CLEARANCE $\frac{1}{4}$ IN.
CARRARA BLACK $\frac{1}{4}$ IN.
PITCO PX 235
PC GLASS BLOCK — DRUID LX75 WITH
FIBERGLAS SCREEN $\frac{3}{4}$ IN.


Exterior Wall Screen.

Made up of opaque and translucent elements with venting at top.

The completed house is the Fourth Prize design, Page 12.




SECTION




ELEVATION

DETAIL



W. BROOKS CAVIN
8310 18th ST.
SILVER SPRING, MD.

SP


fluorescent light
adjustable fixture
plate glass mirror
twindow
glass shelves
counter-type sink
structural glass
vanity drawers

BATHROOM DETAIL

Corner of Bathroom.
Brightly daylighted; broad reflecting surface.
From house design shown on Page 25.



SP

LOUIS C. DIXON & LEE B. KLINE
1181 SOUTH BROADWAY
LOS ANGELES 15, CALIF.




GLASS STAIR DETAIL

Stair-rail Panel of Glass.
The most arresting of the details suggested for using glass with stairs.




Interior Screen to Shield Entrance (see house design, Page 28)
A: light metal frame. B: Continuous plug-in strip. C: Adjustable light. D: Tempered translucent glass. E: Cabinet; sliding doors. F: Steel angles screwed through glass. G: Everseal glass tape. H: Concealed electric conduit. I: Sub-floor electric duct. J: Support connection to duct. K: Finish floor. L: Finish ceiling. M: Connection to upright support. N: Glass block partition.



SEYMOUR R. JOSEPH
1841 BROADWAY
NEW YORK 23, N. Y.



SP



Two types of Partitions Exploiting Characteristics of Glass
For finished house of which this is a detail, see Page 19.


CHARLES G. MacDONALD
QUINBY BLDG.
850 SO. GRAND AVE.
LOS ANGELES, CALIF.

SP




RALPH RAPSON
645 N. MICHIGAN
CHICAGO 11, ILL.

SP



Glass Roof Slot
3'-6" in width; runs along center
for entire length of house.
The entire house is shown on Page
10.



Exterior Wall Panel.
A colorful suggestion; technically
feasible.
See complete house design, Page
20.

CHARLES D. WILEY
1008 NORTH STATE ST.
CHICAGO 18, ILL.

SP

NON-PREMIATED DESIGNS

While the selected drawings shown on the following pages are non-premiated schemes, they do indicate, still further, the trend in contemporary planning. The problem of designing a house, as in the case of this competition, permits literally hundreds of possible solutions. Certain patterns or schemes, however, seem more acceptable than others. It is well, therefore, to keep in mind some general criticisms and suggestions while looking over these designs, and to study each drawing with an appraising eye.

USE OF SITE

Use of the site in most submissions was good. Most designers recognized that privacy, outdoor recreation, gardening and service areas are important essentials to good house planning. However, there were some designers who, from desire for effect, or through faulty planning, placed the bulk of their house so far to the rear of the lot that maximum land usage was not possible.

SIMPLE HOUSEKEEPING

The use of active areas segregated from quiet areas has considerable merit, for it has a tendency to simplify cleaning. Any scheme that has long involved halls may be looked upon with some scepticism for it is often a clue to poor planning and complicated housekeeping. Windows that can't be cleaned easily or are poorly placed, kitchens that are awkwardly arranged, laundries that would require an Amazon to keep clean and to service—were some of the reasons why these drawings may not have been chosen as prize winning designs.

IMPROVED FACILITIES FOR DAILY FAMILY ACTIVITIES

Naturally, easy circulation through the house, quiet and restful sleeping areas, better bathroom planning, and pleasant eating arrangements are important elements which should be provided in every house. Storage space is also important, for there must be places for clothes, games, books and the like. Some arrangement should also be provided for hobbies, recreational facilities, work space and relaxation. Most of these solutions adequately provided for these spaces and areas.

AMUSEMENT AND RECREATIONAL AREAS

It has become more and more apparent, particularly in good contemporary planning, that amusement and recreational areas must be provided. We have gone through that period of the basement game room and have discovered that it is only half the answer. The idea of providing proper play space is good but providing it in the basement has many limitations for it is apt to be damp, out of the way, or hard to keep clean. It is therefore gratifying to note that in the majority of these schemes this problem was solved by some arrangement on the main living floor. A number of designers found that a flexible living-room arrangement was an excellent solution. Others felt that they could give over an entire area for recreation. Perhaps the best solutions were those that permitted either of these schemes and made some possible tie-in with the outdoor play areas.

Outdoor play areas were often muffed. Sometimes adequate outdoor play space was provided but parental supervision was impossible because of its location. In other schemes

outdoor play areas were provided for the children but there was no space for rainy-day playing in the house. A simple arrangement such as a flexible partition between adjoining children's rooms would have been sufficient provision in many cases.

ORIENTATION

The relationship between the points of the compass, the sun and its solar axis and the layout of the rooms themselves have important corollaries. With few exceptions most of the following designs seem to have related these essentials properly.

PRIVACY

As most of these contemporary designs use large glass areas in the living and sleeping spaces it is essential that privacy from neighbors' view should be assured. This may be provided by means of shrubs, trees, or fences. It is probable that living and sleeping areas are not the only places that privacy may be desired. The better arrangements used some type of screening for the service and laundry areas and even for the vegetable garden where it seemed necessary.

COST INDICATIONS







As most of these schemes have about the same square foot area, it is interesting to note how much more expensive certain types of schemes appear than others. There is always the old story of the rambling house, its additional roof and wall area. But perhaps the most glaring single item is the rather expensive bathroom arrangements that keep cropping up. Many of the schemes provided three bathrooms. Many had two very complete ones. It would seem that in a house that was supposedly going to cost between \$6,500 and \$8,000 that the designers should have given more consideration to the cost of so many bathrooms. A single complete bathroom and an extra seat and basin was felt to be sufficient and certainly two complete bathrooms adequate. However, most designers did make use of standard sizes of material, short roof and floor spans, and simple structural details, indicating that economical construction was an important consideration in their thinking.

SUITABILITY TO CLIMATE

Most of the designs submitted in this competition were schemed for some particular area. With notably few exceptions the designers did not provide any impractical arrangements. However, some of those who planned large sliding windows for the northern states should have thought the problem through a little further. Lacking details, it would appear that they were too quick to provide these large windows for effect rather than practicability. Nevertheless, the majority of designers did seem to provide for the climatic limitations of the area chosen.

BETTER LIVING SURROUNDINGS



It is interesting to note that in this competition there were fewer of the "box" modern or international style houses than heretofore. On the whole it seems that the houses have an agreeable domestic character and would be assets to any community.




**PENCIL POINTS
ARCHITECTURAL**

PITTSBURGH COMPETITION

**J. FLOYD YEWELL
10 EAST 40th ST.
NEW YORK, N. Y.**




FLOOR PLAN
SCALE $\frac{1}{8}'' = 1'-0''$



A-435' 16" 696
B-425' 14" 595
C-18' 2" 36
D-13' 3" 39
TOTAL 1366'


FLOOR AREA DIAGRAM




SECTION

ELEVATION

LOCATION MIDDLE ATLANTIC STATES




PLOT PLAN
SCALE $\frac{1}{8}'' = 1'-0''$




PLAN

SLIDING MIRROR DOOR - LIVING TO DINING
SCALE $\frac{1}{8}'' = 1'-0''$



NORTHEAST ELEVATION



NORTHWEST ELEVATION

PENCIL POINTS ■ PITTSBURGH ARCHITECTURAL COMPETITION


ROYAL BARRY WILLS
3 JOY ST.
BOSTON 8, MASS.




SOUTH EAST ELEVATION




NORTH WEST ELEVATION





FIRST FLOOR PLAN




PLOT PLAN
SCALE 1/4\"/>



SECOND FLOOR PLAN





A	10.5 x 22.5	175	A	175	
B	10.5 x 27	284	B	284	
C	10.5 x 12.5 - 4	175	C	175	
D	12 x 12.5 - 6	84	D	25	
TOTAL		724	TOTAL		675



PLAN

DETAIL NORTH
EAST WALL OF
LIVING-DINING
ROOM





SECTION




ELEVATION

PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION

WILLIAM LAKE ADDIKSON
723—THIRD ST.
ROANOKE, VA.




SOUTH AND MIDWEST




DEACIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION

LT. JO RUSSELL M. AMDAL U.S.N.R.
610 H ST. N.E., WASHINGTON 2, D. C.


PENCIL POINTS — PITTSBURGH ARCHITECTURAL COMPETITION





PERSPECTIVE
1/4" = 1'-0"








SHOWER WALL DETAIL
3/4" = 1'-0"



A	11	14	154
B	13	14	174
C	14	29	406
D	10	17	184
E	14	26	364
F	1	4	4
G	1	2	2
H	FURNACE		0
I	2	20	40
J	1/2	3	36
			68
GRAND TOTAL 1593			






Sketch



A HOUSE FOR THE SOUTHWEST PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION

ALDEN B. DOW, INC.
2128 COMMERCE BLDG.
HOUSTON 2, TEX.



1213516




GEORGE FARKAS
 954 41st ST.
 MIAMI BEACH, FLA.

PENCIL POINTS


PITTSBURG ARCHITECTURAL COMPETITION



1ST FLOOR







2ND FLOOR




BASEMENT


A HOUSE IN WESTCHESTER




NORTH WEST




NORTH EAST






ROBERT ST. OWEN BROWN
MAPLE HILL FARM
CARMEL, N. Y.



A VINE-COVERED COTTAGE FOR





THE MIDDLE-WEST ARS LONGA VITA BREVIS




DETAIL OF CLOSET WALL • MASTER BEDROOM ELEVATION


SCALE 3/8" = 1'-0"




PENCIL POINTS • PITTSBURGH GLASS COMPETITION




VIEW FROM SOUTH-EAST



DETAILS




prefab skylight ceiling light unit





A	10'	=	20'	(20' x 10')	200
B	10'	=	10'	(10' x 10')	100
C	10'	=	10'	(10' x 10')	100
D	10'	=	10'	(10' x 10')	100
E	10'	=	10'	(10' x 10')	100
F	10'	=	10'	(10' x 10')	100
TOTAL					496

AREA 1361 sq. ft.



PLAN



PLAN PLAN W - ONE POOL


a house in New Jersey

PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION

KATZ-WAISMAN & ELMALAH
327 LEXINGTON AVE.
NEW YORK, N. Y.

PENCIL POINTS - PITTSBURG


ARCHITECTURAL COMPETITION
HOUSE LOCATED 42' N. COASTAL AREA







STREET ELEV




N W ELEV




S W ELEV




UPPER FL



GROUND FL



PLOT PLAN






SPACE DIAGRAM

ARNOLD TUCKER & A. J. DONAHUE
46 ELGIN ST.
OTTAWA, CANADA





PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION

a house for cheerful living in the pacific northwest





PERSPECTIVE





PITTSBURGH: CORNING PRODUCTS

1. TINKING
2. HEAVY PLATE GLASS DOOR
3. SOLAR HEAT ABSORBING GLASS
4. 1/2" POLISHED PLATE GLASS
5. COPPER BACK MIRRORS
6. 1/2" HEAVY PLATE GLASS ETCHED
7. 1/2" BLACK STRUCTURAL CARARRA GLASS
8. 1/2" BLACK STRUCTURAL CARARRA GLASS
9. GLASS BLOCK
10. GLASS TUBES, FOUNTAIN

KEY TO EQUIPMENT

- a. RANGE
- b. DISHWASHER, SINK, DISPOSAL
- c. REFRIGERATOR
- d. CUPBRETTS
- e. OFFICE
- f. RADIO
- g. FAN
- h. CLOCK
- i. CLOCK
- j. WASHER-DRYER
- k. GAS FURNACE
- l. HOT WATER HEATER
- m. UTILITY SINK
- n. AIR CONDITIONER
- o. TELEPHONE
- p. BOOKS




Identification Symbol

LOCATION: — NORTHERN UNITED STATES AREA

PENCIL POINTS 'PITTSBURGH' ARCHITECTURAL COMPETITION

J. MILTON DYER, JOSEPH CERUTI &
MAURICE CORNELL
1916 E. 71st ST.
CLEVELAND, OHIO




PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION


MINORU YAMASAKI
1524 HENRY AVE.
MAMARONECK, NEW YORK

A black and white architectural sketch of a modern house. The house features a prominent stone chimney on the left side and a large, dark, angular roof structure. The walls are textured with vertical lines, suggesting a material like stone or brick. A large, leafless tree stands to the right of the house, its branches reaching upwards. The foreground shows a low stone wall and some foliage. The overall style is a loose, expressive line drawing.

SUBMITTED
FOR
"G.I. Joe"





SECTION




1	0.30' X	5.33' X .5	0.16 ✓
2	0.30' X	12.30' ✓	01.20 ✓
3	17.33' X	0.33' ✓	1.00 .30 ✓
4	14.30' X	18.00' ✓	2.61.00 ✓
5	11.30' X	11.30' ✓	128.22 ✓
6	11.30' X	3.00' X .5	17.25 ✓
7	0.30' X	6.30' ✓	42.20 ✓
8	24.30' X	10.00' ✓	244.00 ✓
9	30.18' X	14.30' ✓	336.30 ✓
TOTAL SQ. FT. AREA			1203.77
			1393.27

DETAIL OF GLASS WALL
AND BUILT IN CASE AT THE
DINING END OF LIVING RM.

58




READING OR BUFFET




PENCIL POINTS — PITTSBURGH ARCHITECTURAL COMPETITION




JOHN LORING PERKINS
5149 VILLAGE GREEN,
LOS ANGELES 16, CALIF.




WEST PERSPECTIVE




FIRST FLOOR PLAN




SECOND FLOOR PLAN



PLOT PLAN
SCALE: 1/8" = 1'-0"
A HOUSE IN MICHIGAN




SOUTH - EAST




NORTH - EAST

FIRST FLOOR	SECOND FLOOR
<ul style="list-style-type: none"> 6 08 x 30 = 408 6 26 x 27 = 63 6 36 x 28 = 104 6 7 x 6 = 42 6 16 x 15 = 412 6 18 x 3 = 42 6 18 x 6 = 9 6 15 x 7 = 105 6 7 x 7 = 49 TOTAL 1418 	<ul style="list-style-type: none"> 6 40 x 15 = 608 6 7 x 7 = 49 6 18 x 6 = 108 TOTAL 665
<p>COMPUTATIONS OF FLOOR AREAS</p> <p>TOTAL AREA = 10803.00 sq. ft.</p>	

GLASS DETAILS



DINING - LIVING - ROOM
SLIDING WINDOW DETAIL
SCALE: 1/8" = 1'-0"



SECTION A-A

DRAINAGE - GROUND RAIL
 COPPER WEATHERSTRIPPING
 METAL WHITE CHROME FRAME
 FINISH CEILING
 LEATHER HEAD
 STAINLESS STEEL CHANNEL
 METAL FOIL
 PUTTY
 FINISH - 2ND COAT OF PAINT
 INSULATION MATERIAL
 QUARTER TON
 1/2" FLAT GLASS
 1/2" AIR SPACE
 1/2" AIR SPACE


SECTION B-B

DRAINAGE WHITE CHROME FRAME
 PUTTY WEATHERSTRIPPING
 STEEL SPRING
 1/2" FLAT GLASS
 1/2" AIR SPACE

SECTION C-C

DRAINAGE WHITE CHROME FRAME
 1/2" STEEL CHANNEL
 1/2" AIR SPACE
 COPPER WEATHERSTRIPPING
 FINISH FLOOR
 1/2" WEED BOARD
 DRAINAGE GROUND RAIL






WINDOW SECTIONS
FULL SCALE



STORAGE WALL
DETAIL

PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION


CHARLES T. GRANGER, GEORGE MATSUMOTO
 & E. W. WAUGH
 CRANBROOK ACADEMY OF ART
 BLOOMFIELD HILLS, MICH.



PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION


HOUSE FOR G.I. JOE IN SOUTHWESTERN VIRGINIA - BY - HAM * PAW

CHARLES A. PEARSON JR.
RADFORD, VA.




PENCIL POINTS "PITTSBURGH" ARCHITECTURAL COMPETITION

NOTE FOR MIDDLE ATLANTIC DESIGN
with
CONTROLLED SOLAR HEATING
CEILING PANEL HEATING
W/ MODULAR CONSTRUCTION




MASONRY
(G.L.F. with this help of exterior wall
build this part in two equal times)

CARPENTRY
(Joinery with timbers, use 5
residual dimensions + simple
construction)




CUBAGE
1000 cu. ft.



DETAILS - WOOD & GLASS EXTERIOR WALLS - CLOSETS

PERCIVAL GOODMAN
18 EAST 40th ST.
NEW YORK, N. Y.




PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION

NOT ON PLUMB
Gee Whiz






ANTONIN RAYMOND, YUSUF MEER
 & EARL H. STRUNK
 101 PARK AVE.
 NEW YORK 17, N. Y.








PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION

LT. COMDR. SAMUEL E. HOMSEY U.S.N.R.
610 H. ST., N.E.
WASHINGTON, D. C.




PENCIL POINTS — PITTSBURGH ARCHITECTURAL COMPETITION

PHILIP C. JOHNSON
205 E. 42nd St.
NEW YORK 17, N. Y.




NORTHWEST ELEVATION




SOUTHWEST ELEV.

1	26' x 21' = 546
2	14'5" x 3' = 44
3	4'5" x 14' = 63
4	15'4" x 30' = 459
5	4' x 10' = 40
6	3' x 4' = 12
7	10' x 2' = 20
8	8'5" x 12' = 102
9	11' x 12' = 132
TOTAL = 1392	



DINING SPACE ELEVATION

SECTION



PLAN













GLASS ENTRY SCREEN

LOCATION: UNITED STATES




PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION

SIMON BREINES
POMERANCE & BREINES
18 E. 48th ST., NEW YORK, N. Y.





PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION

GABRIEL F. MASSENA
704 DELAWARE AVE.
WILMINGTON, DEL.




Pencil Points "Pittsburgh" Architectural Competition




FLOOR AREA

A	40'-28	1120
B	15'-12-5	186
C	13'-4	52
D	25'-8	20
E	11'-5-1/2	-27
F	5'-5	-28
G	4'-10	-40
H	15'-10-1/2	75
TOTAL	-95	1450 - 1360"




NORTHWEST ELEVATION $\frac{1}{8}''=1'-0''$ STREET ELEVATION

DONALD HERSHEY
5 LANDING ROAD SO.
ROCHESTER 10, N. Y.




PERSPECTIVE FROM SOUTH



FLOOR PLAN AND PLOT PLAN
A HOUSE FOR THE SOUTHWEST

AREA COMPUTATION




A	19.75 x 37.0'	730.75
B	10 x 60'	12.0
C	75 x 19.5'	146.25
D	150 x 28.0'	540.0
E	105 x 12.5'	131.25
F	60 x 70 x 1/2'	21.0
TOTAL AREA		1586.25 SQ. FT.




NORTH-EAST ELEVATION




NORTH-WEST ELEVATION



ELEVATION
DETAIL OF ENTRANCE



SECTION A-A




PLAN

PENCIL POINTS
ARCHITECTURAL






PITTSBURGH
COMPUTATION

CHARLES T. GRANGER, GEORGE MATSUMOTO
& E. W. WAUGH
CRANBROOK ACADEMY OF ART
BLOOMFIELD HILLS, MICH.



PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION




DWIGHT E. STEVENS
205 WILLIS ST.
STILLWATER, OKLA.



AREA TABULATION


A	17'0" x 31'4"	532.68
B	15'0" x 12'8"	240.50
C	9'6" x 18'8"	129.78
D	12'0" x 8'4"	100.80
E	9'6" x 40'0"	384.00
F	15'0" x 6'0"	90.00
G	6'4" x 7'6"	47.42
H	7'0" x 7'6"	52.50
I	11'4" x 7'0"	80.38
TOTAL		1570.72

GEOGRAPHIC LOCATION
SOUTHERN WISCONSIN
WHERE STONE QUARRIES
ARE COMMON.







PENCIL POINTS • PITTSBURGH • ARCHITECTURAL COMPETITION

CHARLES H. DORNBUSCH & WM. J. McARTHUR
333 N. MICHIGAN AVE.
CHICAGO, ILL.




FREDERIC H. KOCK
1304 CAREW TOWER
CINCINNATI, OHIO




PENCIL POINTS • PITTSBURGH ARCHITECTURAL COMPETITION



GREVILLE RICKARD
139 EAST 53rd ST.
NEW YORK, N. Y.



View from South




Floor Plan 1/4"




Street Plot Plan 1/4"




Northwest




Northeast




Section



Detail Plan 1/4"




Perspective of detail




Elevation Detail at Serving Counter 1/4"

PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION



LESLIE ARTHUR
3001 MAXWELL ST.
LOS ANGELES 27, CALIF.












ALFRED CLAUSS & JANE WEST CLAUSS
LITTLE SWITZERLAND
R. 9 KNOXVILLE, TENN.



LOUIS C. DIXON & LEE B. KLINE
1151 SOUTH BROADWAY
LOS ANGELES 18, CALIF.






MULTI-USE ROOM
ALTERNATES



PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION





MID-WEST
NOM-06
GUESS

MATERN, GRAFF & YORK
9004-161st ST.
JAMAICA 2, L. I., N. Y.




• PENCIL • POINTS - PITTSBURGH • ARCHITECTURAL • COMPETITION •




RUSSEL H. HIETT
402 WEST 18th ST.
HUTCHINSON, KANSAS



AREA
A. 15' x 33' = 512
D. 26' x 34' = 884
TOTAL 1396




A HOUSE FOR THE
SOUTHWESTERN
PART OF THE
UNITED STATES




PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION

GEORGE C. ANDERSEN
1135 NINTH ST.
SANTA MONICA, CALIF.



LOUIS C. DIXON & LEE B. KLINE
1181 SOUTH BROADWAY
LOS ANGELES 18, CALIF.





SOUTH WEST ELEVATION



SOUTH EAST ELEVATION




NORTH WEST ELEVATION



ELEVATION A

SECTION 1-1


ELEVATION B




PLAN

DETAIL OF DR. R. UNIT

1" = 8" 1/2"



AREA
A = 24'0" x 30'0" = 720'0"
B = 14'0" x 49'0" = 686'0"
MIROR C. 8'0" x 4'0" = 32'0"
TOTAL SQ. FT. 1397.5'0"





PLOT PLAN


SOUTHERN CALIFORNIA

PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION


JOHN E. FORTUNE
5900 ECHO ST.
LOS ANGELES, CALIF.



N. EAST ELEVATION




NEWEST ELEVATION




PHOT. PLAN



BASEMENT



ELEVATION



PLAN
DETAIL OF FIREPLACE BOOK SHELVES ETC.

A _____

B _____

C _____





D _____

E _____



T _____

PENCIL POINTS PITTSBURGH
ARCHITECTURAL COMPETITION

WALTER J. THIES
3117 N. MAIN ST.
DAYTON 5, OHIO



FIRST	
A 35'-15 1/2"	9037
B-C 16'-21" - 34'-4"	374
D 32'-5"	7
E 28'-16 1/2"	68
F 15'-11 1/2"	6 1/2
G 28'-23"	1 1/2
H 2'-6"	40
F 4'-11 1/2"	51
TOTAL	791.01
SECOND	
13'-16"	370
TOTAL BOTH FLOORS 1309.01 sq ft	



LOCATION—NORTH CENTRAL



AREA

PLOT
1/2" = 1'-0"

SUBMITTED BY

"PENCIL POINTS"—PITTSBURGH ARCHITECTURAL COMPETITION




RICHARD H. MARR & CARL B. MARR
416 BRAINARD ST.
DETROIT 1, MICH.








PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION

**OSCAR STONOROV & LOUIS I. KAHN
BULLETIN BLDG.
PHILADELPHIA 7, PA.**



PENCIL POINTS 'PITTSBURGH' ARCHITECTURAL COMPETITION



FOR THE GREAT LAKES REGION



MARVIN R. DOBBERMAN
205 TELEGRAM BLDG.
SUPERIOR, WISC.



• PLOT PLAN •
SCALE: 1/4" = 1'-0"

• PENCIL POINTS • PITTSBURGH • • ARCHITECTURAL COMPETITION • • A HOUSE IN • • NORTH CAROLINA •

A	20' x 34'	=	680.00	SQ. FT.
B	15' x 25'	=	375.00	
C	17' x 20'	=	340.00	
D	17' x 12'	=	204.00	
E	35' x 6'	=	210.00	
F	15' x 20'	=	300.00	
TOTAL		=	1338.75	SQ. FT.


• AREAS •




• SOUTHWEST ELEVATION •



• NORTHWEST ELEVATION •




• FLOOR PLAN •




• CHILDREN'S BATH •




• PARENTS' BATH •




• KITCHEN •



• DINING •



• TABLE •



NOTE: MIRROR TABLE TOP • SANDBLASTED • DESIGN •

• PLAN • • SECTION • • ELEVATION •


• DETAILS OF SCREEN IN DINING ROOM •

PENCIL POINTS-PITTSBURGH ARCHITECTURAL COMPETITION



STATION PT. 100'-0" S.W. BY 5 FROM CORNER A OF BED RM WING.

VIEW OF S.W. AND S.E. SIDES OF G.I. JOE'S COTTAGE.





NORTH EAST (STREET) ELEVATION

SCALE $\frac{1}{8} = 1'-0"$



NORTH WEST ELEVATION



A HOUSE FOR CHEERFUL LIVING PLAN+PLOT PLAN AT $\frac{1}{8} = 1'-0"$ INDEX OF LETTERS ON PLAN

SPACE	SIZE	AREA	CLOS.	GLASS	MIRRORS
A	STATION POINT. A' = S.E. CORNER OF BED RM WING. SOUTH VIEW.				
B	2 BATHS, EACH 5' x 7'	70	10	10	10
C	FOR. POR. JOE'S RM. 13' x 15' (incl. 19' x 21' 1/2" x 22' 1/2")	195	2	2	2
D	315' RM. 10' x 11'	110	2	2	2
E	JUNIOR'S RM. 9' x 10'	90	1	1	1
F	DINING RM. 11' x 13'	143	3	3	3
G	ENTRY. GARAGE TO HOUSE 5' x 6'	30	4	4	4
H	FAMILY COAT CLOSET 2' x 6'	12	4	4	4
I	GARAGE. 1 CAR. VINYL FLOOR 17'	187	4	4	4
J	GAS HEATER FOR CIRCULATING HOT WATER HEAT + PLUMBING HOT WATER.				
K	KITCHEN INC. 2 CLOS. 10' x 12 1/2'	126	4	4	4
L	LIVING ROOM 15' x 21 1/2'	319	4	4	4
M	MIRRORS SHOWN ON $\frac{1}{8}$ SCALE PLAN BY SYMBOL.				
N	PERGOLA. OPEN ROOF. 11' x 17'	187	4	4	4
O	QUERCUS - LARGE OAK TREE. FOR SHADE IN SPAC. FOR OUTDOOR LIVING.				
P	STORAGE SPACE IN ROUGH ATTIC OVER GARAGE. BELLIER STAIRS OVER THIS.				
Q	2 WASH TUBS.				
R	W. LINEN CLOSET 2 1/2' x 5'. U. UTILITY - BROOM CLOSET 2' x 3'.				
S	VESTIBULE OF FRONT ENTRANCE 5' x 9' 4 1/2" COAT CL. 2 1/2' x 1 1/2' 20' x 2 1/2' HRS. ETC. 25'				
T	WOOD FOR L.R. FIREPLACE. STACKED IN GARAGE. CAN BE REACHED FROM DOOR IN L.R.				


DIAGRAM

a	5' x 12' = 60
b	8 1/2' x 22 1/2' = 191.25
c	20' x 30' = 1,363
TOTAL AREA	= 1,614.25
LESS h	= 217.00
NET AREA	= 1,397.25

NOM-DE-GUERRE:
OLD SALT
GEOGRAPHICAL LOCATION:
SUFFOLK COUNTY,
LONG ISLAND
NEW YORK.

ARCHIBALD MANNING BROWN
150 E. 81st ST.
NEW YORK 21, N. Y.

VIEW FROM
NORTHEAST




FLOOR PLAN

PENCIL POINTS-PITTSBURGH ARCHITECTURAL COMPETITION



LOCATION
CALIFORNIA



PLOT PLAN



PLAN




SOUTHEAST
ELEVATION




NORTHWEST
ELEVATION

INSIDE FLR AREAS

①	0-26 - 972.0
②	0-25 - 60.8
③	0-24 - 318.0
④	0-23 - 229.0
⑤	0-22 - 27.0
TOTAL AREA	1598.5



NOM DE
GUERRE





SECTION 'A'


ELEVATION

DETAILS OF GLASS SCREEN
BETW. ENTRY & ALL PURPOSE RM


BENJAMIN H. STEIN
742 DELAWARE
DETROIT 2, MICH.



NORTH ELEVATION



WEST ELEVATION




DETAIL OF BATH RECESS

PENCIL POINTS-PITTSBURGH ARCHITECTURAL COMPETITION


ASSUMED GEOGRAPHICAL LOCATION IS CALIFORNIA


NOM-DE-GUERRE


T. GERALD KRONICK
2740 FULLERTON AVE.
DETROIT, MICH.



SECTION - DETAIL "A"




ELEVATION B-B - FROM LIVING ROOM



COMPUTING FLOOR AREA

AREA A	- 24' x 41' = 1004	30 FT
B	- 11' x 11' = 121	
C	- 10' x 12' = 120	
D	- 3' x 11' = 33	
E	- 2' x 5' = 10	
F	- 4' x 2' = 8	
TOTAL	1396	30 FT




PLAN




PERSPECTIVE


PUGET SOUND - PACIFIC NORTHWEST



BASEMENT



PLOT PLAN



FLOOR PLAN



SIDE ELEVATION







REAR ELEVATION

PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION


ALFRED F. SIMONSON
3936 WOODLAND PARK AVE.
SEATTLE 3, WASH.

NORTHERN U.S.





IT HAD RECENTLY BEEN DISCOVERED THAT A TREE WOULD SHED ITS LEAVES AT ABOUT THE TIME WE WOULD MOSTLY BE OUT IN OUR BOWLS. PLANS ARE BEING Laid TO DETERMINE WHAT SPRING WINTER, THE LEAVES WILL BEATFALL IN TIME TO SHUT OUT THE HOT SUMMER SUN.



NORTHEAST ELEVATION





NORTHWEST ELEVATION



AREA COMPUTATION	
AREA A' 10.46 - 720.0	
17.55' 24.9 - 18	
17.55' 11.64 - 65	
AREA PER FLOOR - 695.5	
TWO FLOORS - 1391.0	


BASMENT & GARAGE AREAS NOT COMPUTED




SLIDING MAGNOLITE PANELS SHIELD VIEW INTO KITCHEN WITHOUT OBSTRUCTING LIGHT TO COUNTER. WHEN OPEN ENTIRE AREA IS ONE LARGE ROOM FOR WORK AND PLAY. WHEN CLOSED EACH AREA ENJOYS PRIVACY...HINGED FLAPS COVER TRACKS, MAKING LEVEL COUNTER FOR MEALS, MIDNIGHT SNACKS OR SOME MARTINIS.

PENCIL POINTS-PITTSBURGH ARCHITECTURAL COMPETITION

L. MORGAN YOST & AUBREY TUPPER-WHITE
363 RIDGE ROAD
KENILWORTH, ILL.



• P E R S P E C T I V E • F R O M • N O R T H E A S T •




• F L O O R • A N D • P L O T • P L A N •




• S O U T H E A S T • E L E V A T I O N •



• N O R T H W E S T • E L E V A T I O N •




• L I V I N G • D I N I N G • R O O M • W A L L • D E T A I L •




• A R E A • D I A G R A M •

PENCIL POINTS-PITTSBURGH ARCHITECTURAL COMPETITION


... LOCATION ... / EAST - MIDWEST ...




VIEW FROM THE LIVING GARDEN LOOKING SOUTH




PLAN OF FIRST FLOOR AND LAYOUT OF PLOT PLAN




ELEVATION




SECTION



NORTH WEST ELEVATION



NORTH EAST ELEVATION




PLAN

DETAIL DRAWING OF SLIDING SASH OPENING TO THE LIVING GARDEN FROM THE PASSAGE ALONG SIDE OF THE BED ROOMS THEREBY PROVIDING THROUGH VENTILATION FOR ALL BED ROOMS WHEN IT IS DESIRED

CUBAGE COMPUTATIONS

A	57' x 15' = 855'
B	15' x 23' = 345'
C	4' x 12' = 48'
D	2' x 12' = 24'
E	6' x 12' = 72'
TOTAL	1385'

LOCATION - MIDDLE ATLANTIC STATE




SYMBOL


**PENCIL POINTS
ARCHITECTURAL**

**- PITTSBURGH
COMPETITION**

JOHN HIRONIMUS
621 EAST BLACKFORD AVE.
EVANSVILLE, IND.




PLOT PLAN




FIRST FLOOR SECOND FLOOR
 A = 14'-6" x 27'-0" = 661.5 SQ. FT.
 D = 12'-6" x 11'-6" = 145.75 " "
 C = 8'-6" x 9'-0" = 76.5 " " = HEATING ROOM
 D = 24'-10" x 27'-0" = 670.5
 (A-C) + D + D = 1599.25 SQ. FT.


FLOOR AREAS




FIRST FLOOR PLAN



SECOND FLOOR



SECTION A-A ELEVATION DRESSING TABLE



DETAIL






REAR ELEVATION SIDE ELEVATION

PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION

LOCATION
 N. CAROLINA



M. RIGHTON SWICEGOOD
 851 GRAND CONCOURSE
 BRONX, NEW YORK




DETAIL OF G. I. JOES TROPHY CASE IN LIVING ROOM.

FLOOR AREA	
A - 10'x16' - 416.0	
B - 11'x14' - 314.8	
C - 12'x12' - 346.0	
D - 8'x8' - 64.0	
Total sq. ft.	1342.8

PENCIL POINTS ♦ PITTSBURGH
♦ ARCHITECTURAL ♦ COMPETITION ♦

A HOUSE FOR
CHEERFUL
LIVING -
LOCATION CALIFORNIA
Submitted by


R. W. TEMPEST
1411 EAST JEFFERSON AVE.
DETROIT 7, MICH.



NORTHWEST




NORTHEAST




FIRST FLOOR


BASINMENT FOR HEATER
STORAGE SPACE AND
RECREATION SPACE
USED IN BAD WEATHER




SECOND FLOOR



PLOT PLAN





DETAIL OF LAVATORY



KITCHEN AND BATHROOM SIMILAR

MATERIALS BYT
FIGURED PLATE GLASS RAILING BETWEEN LANDING & SECOND FLOOR




A - 25' x 27' - 675' -
Total square feet 1350 -
FLOOR AREA

A HOUSE FOR
CHEERFUL LIVING
IN SOUTHERN
OHIO


Submitted by

PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION

R. W. TEMPEST
1411 EAST JEFFERSON AVE.
DETROIT 7, MICH.



PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION




SOUTHEAST

MIDDLE WEST
BUY WAR BONDS
HOW DE QUINCE



NORTHWEST


SOUTHWEST



GLYDE A. STOODY
831 CARYL DRIVE
PITTSBURGH 10, PA.




PERSPECTIVE FROM STREET




NORTHWEST ELEVATION




SOUTHWEST ELEVATION




FIRST FLOOR



SECOND FLOOR




PLOT




AREA DIAGRAMS

AREA CALCULATION


FIRST FLOOR	
A - 10'6" x 12'0" =	126.00
LEG B - 10'0" x 12'0" =	120.00
LEG C - 10'0" x 12'0" =	120.00
SECOND FLOOR	
C - 10'0" x 12'0" =	120.00
TOTAL	386.00



ELEVATION



SECTION






PLAN





LOCATION: MIDWEST
"LITTLE JOE"

PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION



SAMUEL LADD
7220 TULANE AVE.
UNIVERSITY CITY 8, MO.




LOCATION -
CALIFORNIA



SUBMITTED BY -
"KLUXON"




INTERIOR GLASS DETAIL
STORAGE CABINET IN KITCHEN




PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION


LOUIS C. DIXON & LEE B. KLINE
1151 SOUTH BROADWAY
LOS ANGELES 16, CALIF.







PLOT PLAN



FIRST FLOOR



SECOND FLOOR




ELEVATION


KITCHEN CABINET




SOUTH



EAST



NORTHEAST




SOUTHEAST







NORTHWEST

PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION




E. H. & M. K. HUNTER
MUSGROVE BUILDING
HANOVER, N. H.

*



AREA



A	25.5 x 25.5	650
B	14 x 14.5	203
C	8 x 18	144
D	7 x 4	28
E	4 x 10	40
F	13 x 12.5	162
G	11.5 x 10.5	120
H	8.5 x 12	102
TOTAL		1385




PIVOTED GLASS PARTITION AT MULTI-USE ROOM

PENCIL POINTS — PITTSBURGH ARCHITECTURAL COMPETITION

CHARLES W. LORENZ
911 LOCUST ST.
ST. LOUIS 1, MO.




NORTH ELEVATION




WEST ELEVATION



LOCALE.....
CALIFORNIA






TOTAL FOOTAGE
1399.9' 60 FEET




ELEVATION SECTION
DETAIL DINING ROOM BUFFET

PENCIL POINTS PITTSBURGH ARCHITECTURAL COMPETITION


**LOUIS C. SIMMEL JR.
& DOUGLAS McFARLAND
414 QUINBY BLDG.
LOS ANGELES, CALIF.**



ELEVATION




SECTION




PLAN

DETAIL OF PROJECTING PLANT WINDOW



COMPUTATION OF AREAS		
A	100' x 150'	15000
B	8.5' x 14.5'	1232.5
C	10.5' x 160'	1680
D	15.5' x 208'	3224
E	8.5' x 14.5'	1232.5
F	40' x 4.5'	180
G	70' x 8.5'	595
H	10' x 1.5'	15
I	60' x 4.0'	240
J	15.5' x 15.5'	242.25
K	80' x 40' x 2	1600
L	40' x 0.8'	32
M	2.5' x 40'	100
N	2.5' x 40'	100
TOTAL AREA		11252.25

ASSUMED LOCATION
SOUTHERN
CALIFORNIA

SUBMITTED BY 



FRONT ELEVATION



SIDE ELEVATION

PENCIL POINTS · PITTSBURGH ARCHITECTURAL COMPETITION


BURTON ASHFORD BUGBEE
121 E. 54th ST.
NEW YORK 22, N. Y.





2

FRONT


SIDE




VICTORY GARDEN



ELEVATION



PLAN




SECTION

DETAIL OF PICTURE WINDOW & AWNING BOX

SCALE OF DETAIL
0 1 2 3 4 5

SCALE OF PLAN & ELEVATIONS
0 5 10 15 20

AREA



A	3' x 9' 2 1/2'	27.75'
B	3' x 12'	36 -
C	6' 0" x 56' 3/4'	761.50 -
D	4' x 6' 3/4'	26 -
E	15' x 10'	210 -
F	5' x 19' 5"	97.50 -
G	8' x 9'	72 -
H	2' x 15'	30.50 -











TOTAL

1349.25'

LONG ISLAND




PENCIL POINTS-PITTSBURGH ARCHITECTURAL COMPETITION

RICHARD HAVILAND SMYTHE
1 EAST 53rd ST.
NEW YORK 22, N. Y.




PENCIL POINTS — PITTSBURGH ARCHITECTURAL COMPETITION

PAUL HAYNES
315 W. 9th ST.
LOS ANGELES 15, CALIF.




PENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION


NORMAN W. ALPAUGH
4222 HALDDALE AVE.
LOS ANGELES, CALIF.





SUBMITTED BY




GROUND FLR. PLAN



DINING RM. WINDOW




BASEMENT




PLOT PLAN

LOCATION - MIDDLE ATLANTIC STATES




AREAS

A	- 15' x 10'	= 150
B	- 12' x 10'	= 120
C	- 48' x 10'	= 480
D	- 17' x 10'	= 170
TOTAL		= 920




FRONT ELEVATION




SIDE ELEVATION

ENCIL POINTS - PITTSBURGH ARCHITECTURAL COMPETITION





CHARLES W. BRESTON
MORRISTOWN, CONN.



PENCIL PITTSBURGH ARCHITECTURAL POINTS PITTSBURGH COMPETITION ~




ALLAN McDOWELL & GEORGE H. VAN ANDA
KENT, CONN.



BASEMENT PLAN



LOCATION
SOUTH CENTRAL OHIO-INDIANA



AREA TABULATION

A	15 x 4.4	660.00	SQ. FT.
B	17.5 x 26.5	463.75	" "
C	14.5 x 16	232.00	" "
D	3 x 7	21.00	" "
E	4 x 7.4 + 2	14.80	" "
F	3 x 5 + 2	7.50	" "
TOTAL AREA		1399.05	SQ. FT.




NORTHWEST ELEVATION





NORTHEAST ELEVATION

PENCIL POINTS — PITTSBURGH ARCHITECTURAL COMPETITION





PENCIL POINTS -
PITTSBURGH ARCHITECTURAL
COMPETITION
NON-DE-OBSCURE
UTYA-IPG
LOCATION - NEW ENGLAND

FIRST	640'
SECOND	574'
TOTAL	1500'



SUN CONTROL - DETAILS
PLAN SCALE 1/4" 12"



MARCEL BREUER
430 EAST 80th ST.
NEW YORK 28, N. Y.

INDEX OF DESIGNERS

FIRST PRIZE

Fletcher, J. B. & Fletcher, N. 6

SECOND PRIZE

Pei, I. M., & Roth, F. G. 8

THIRD PRIZE

Rapson, R. 10

FOURTH PRIZE

Catalano, E. F. 12

SPECIAL MENTION

Belser, K. J., & Dekker, K. H. 14
 Dekker, K. H., & Belser, K. J. 14
 Dukelski, A. 15
 Fordyce, A., & Hyzen, L. 16
 Hyzen, L., & Fordyce, A. 16
 Kazdailis, S. A. 17
 Lundquist, O. 18
 MacDonald, C. G. 19
 Wiley, C. D. 20

MENTION

Babb, E. 21
 Barthelme, D. 22
 Biggs, T. J. 23
 Campbell, B. L. 24
 Cavin, W. B. 25
 Chau, C. N. 26
 Cooling, A. A. 27
 De Felice, T., Harris, M. M., & Schmiderer, S. 33
 Elliott, E. P., & Simpson, D. C. 34
 Granger, C. T., Matsumoto, G., & Waugh, E. W. 36
 Harris, M. M., De Felice, T., & Schmiderer, S. 33
 Joseph, S. R. 28
 Kling, V. 29
 Marshall, P. A. 30
 Matsumoto, G., Granger, C. T., & Waugh, E. W. 36
 Pei, I. J., & Roth, F. G. 32
 Perkins, C. S. 31
 Roth, F. G., & Pei, I. M. 32
 Schmiderer, S., De Felice, T., & Harris, M. M. 33
 Simpson, D. C., & Elliott, E. P. 34
 Stein, J. A. 35
 Waugh, E. W., & Granger, C. T., & Matsumoto, G. 36
 Weiss, F. 37, 38

SPECIAL PRIZE

Catalano, E. F. 39
 Cavin, W. B. 39
 Dixon, L. C., & Kline, L. B. 40
 Joseph, S. R. 40
 Kline, L. B., & Dixon, L. C. 40
 MacDonald, C. G. 41
 Pei, I. M., & Roth, F. G. 41
 Rapson, R. 42
 Roth, F. G., & Pei, I. M. 41
 Wiley, C. D. 42

NON-PREMIATED

Addikson, W. L. 46
 Alling, S. J. 58
 Alpaugh, N. W. 110
 Amdal, R. M. 47
 Andersen, G. C. 81
 Arthur, L. 76
 Beeston, C. W. 111
 Besinger, C. 52
 Bines, S. 67
 Buer, M. 114

Brown, A. M. 89
 Brown, R. St. O. 51
 Bugbee, B. A. 107
 Ceruti, J., & Dyer, J. M. 56
 Clauss, A., & Clauss, J. W. 77
 Cunningham, P. 113
 Dixon, L. C., & Kline, L. B. 78, 82, 103
 Dobberman, M. R. 87
 Donahue, A. J., & Tucker, A. 54
 Dornbusch, C. H., & McArthur, W. J. 73
 Dow, A. B., Inc. 49
 Dyer, J. M., & Ceruti, J. 56
 Elmaleh, Katz & Waisman 53
 Farkas, G. 50
 Fendya, J. J. 94
 Folsom, J. W. 48
 Fortune, J. E. 83
 Garbe, R. W. 97
 Goodman, P. 62
 Graff, Matern & York 79
 Granger, C. T., Matsumoto, G., Waugh, E. W. 60, 71
 Haynes, P. 109
 Hershey, D. 69
 Hiett, R. H. 80
 Hironimus, J. 95
 Homsey, S. E. 65
 Hunter, E. H., & Hunter, M. K. 104
 Johnson, P. C. 66
 Kahn, L. I., & Stonorov, O. 86
 Katz, Waisman & Elmaleh 53
 Kline, L. B., & Dixon, L. C. 78, 82, 103
 Kock, F. H. 74
 Kronick, T. G. 91
 Ladd, S. 101
 Langhorst, L., & Langhorst, F. 102
 Lorenz, C. W. 105
 Marr, R. H., & Marr, C. B. 85
 Massena, G. F. 68
 Matern, Graff & York 79
 Matsumoto, G., Granger, C. T., & Waugh, E. W. 60, 71
 McArthur, W. J., & Dornbusch, C. H. 73
 McDowell, A., & Van Anda, G. H. 112
 McFarland, D., & Simmel, L. C. 106
 McLaughlin, G. W., & Reisner, J. S. 64
 Meer, Y., Raymond, A., & Strunk, E. H. 63
 Pearson, C. A. 61
 Perkins, J. L. 59
 Pugh, E. St. C. 88
 Raymond, A., Meer, Y., & Strunk, E. H. 63
 Reisner, J. S., & McLaughlin, G. W. 64
 Rickard, G. 75
 Robinson, D-W. C. 55
 Simmel, L. C., & McFarland, D. 106
 Simonson, A. F. 92
 Smythe, R. H. 108
 Stein, B. H. 90
 Stevens, D. E. 72
 Stonorov, O., & Kahn, L. I. 86
 Stoody, C. A. 100
 Strunk, E. H., Meer, Y., & Raymond, A. 63
 Swicegood, M. R. 96
 Tempest, R. W. 98, 99
 Thies, W. J. 84
 Tucker, A., & Donahue, A. J. 54
 Tupper-White, A., & Yost, L. M. 93
 Van Anda, G. H., & McDowell, A. 112
 Waisman, Elmaleh & Katz 53
 Waugh, E. W., Granger, C. T., & Matsumoto, G. 60, 71
 Whitaker, E. L. 70
 Wills, R. B. 45
 Yamasaki, M. 57
 Yewell, J. F. 44
 York, Matern & Graff 79
 Yost, L. M., & Tupper-White, A. 93

OTHER REINHOLD BOOKS ON ARCHITECTURE AND CITY PLANNING

architecture

Hospitals—Integrated Design

by Isadore Rosenfield

308 pages, 9 x 12, Illustrated, \$10.75

Apartment Houses

by Joseph Abel and Fred N. Severud

In preparation

Shops and Stores

by Morris Ketchum, Jr.

In preparation

U. N. Headquarters

by Le Corbusier

In preparation

Search for Form

by Eliel Saarinen

In preparation

So You Want to Build a School

by John Lyon Reid and Charles Wesley Bursch

In preparation

Thermal Insulation of Buildings

by Paul Dunham Close 100 pages, 6 x 9, Illustrated, \$1.75

This Business of Architecture

by Royal Barry Wills 210 pages, 6 x 9, Illustrated, \$3.00

Don Graf Data Sheets

779 pages, 4 x 7, Illustrated, \$6.00

city planning

New City Patterns

by S. E. Sanders and A. J. Rabuck

200 pages, 8½ x 11, Illustrated, \$8.00

Housing and Citizenship—

A Study in Low-Cost Housing

by Major George Herbert Gray

250 pages, 8½ x 11½, Illustrated, \$7.50

The Art of Building Cities

by Camillo Sitte—Translated from the German by Lt. Charles
T. Stewart, USNR, former Director, The Urban Land
Institute 130 pages, 8½ x 9¼, Illustrated, \$6.00

Cities of Latin America—

Housing and Planning to the South

by Francis Violich

376 pages, 6 x 9, Illustrated, \$3.75

The City—Its Growth, Its Decay, Its Future

by Eliel Saarinen

379 pages, 6 x 9, Illustrated, \$3.75

UNIVERSAL
LIBRARY



142 024

UNIVERSAL
LIBRARY